



## TRIPURA GRAMIN BANK

HEAD OFFICE: ABHOYNAGAR:

AGARTALA-799005

WWW.TRIPURAGRAMINBANK.ORG

### **Tender Notice for calling tenders for installation of fire and life safety measures at TGB Bardowali and currency chest:-**

Tripura Gramin Bank invites Quotations/Tenders from vendors, having previous experience, for installation of Fire and Life safety measures at TGB Bardowali Branch and Currency Chest at Bardowali. The vendors may submit their tender/ quotation in sealed envelope super scribed "**Quotation/Tender for installation of fire and life safety measures at TGB Bardowali and currency chest**" addressed to the General Manager, Tripura Gramin Bank, Head Office, Agartala, West Tripura, Pin-799005. Vendors are also requested to submit work completion/experience certificate of their previous works.

Last Date of Submitting Quotation/Tender : 08.04.2021(02:00 P.M.)  
Date of opening of Quotation/Tender : 08.04.2021(03.00 P.M.)  
Place of opening of tender/ quotation : Head Office, Tripura Gramin Bank,  
Abhoynagar, Agartala, West Tripura

Encl:

1. Blank Tender for installation of fire and life safety measures at TGB Bardowali and currency chest

Notice date: 26.03.2021

For & on behalf of  
Tripura Gramin Bank

  
H. O. D. (DEV.)

26/03/2021

S.N	Description of items	Rate	Amount
	<b>Installation of Fire and Life Safety Measures at TGB Bardowali Branch and Currency Chest</b>	<b>(In Rs.)</b>	<b>(In Rs.)</b>
1.	One(1) no CO2 Fire extinguisher having capacity 4.5 kg		
2.	One(1) no CO2 Fire extinguisher having capacity 2 kg		
3.	Seven(7) no ABC fire extinguisher having capacity 6 kg		
4.	Seven(7) no ABC fire extinguisher having capacity 2 kg		
5.	One(1) no modular fire extinguisher having capacity 5 kg		
6.	One (1) point 30 mtrs. long and 20 mm dia Hose Reel Hose System to be installed floor wise along with accessories i.e. 02 nos. delivery hose and 01 nos. branch should be housed in double door hose box which to be provided near hose reel point. 01 noi landing valve and pressure gauge to be provided near every hose reel point in each floor(two floors)		
7.	Terrace level water tank having capacity 10000 ltrs. To be installed connected with pump having discharge capacity of 450LPM with pressure 3.5KG/sq cm, starting auto pump controller to be connected with pump.		
8.	Two (2) ways fire inlet to be installed in front side of the building		
9.	Manually operated electronic fire alarm system floor wise(2 floors)		
10.	Air release valve to be installed at terrace of the building		
11.	Down comer system to be installed in the building with mild steel pipe measuring shall be 100 mm/4 inch dia /4.6 mm thickness		



## LIST OF APPROVED MATERIALS & MANUFACTURERS

1. BIS certified Fire extinguisher of Secure Zone/ Saiex or similar quality

### NOTE :

1. GST extra as applicable.
2. All the payments will be subject to provisions of TDS/TCS of Income Tax Act, 1961 as per applicable rates in force.
3. Service Provider (Vendor) will be liable for all applicable taxes as may be applicable on said supply of goods and services to the Bank.
4. Contractor shall complete the work within 4 weeks from the date of work allotted to him.
5. In case work is not completed within prescribed time, contractor shall penalized Rs.1000.00 per day.

